VAV CONNECTION SCHEDULE

Conditional design flows and saved native-plan connections

Flows: L/s | Lengths: m, straight XY centre-to-centre | Drawing units: mm | A4 landscape 1:1

VAV	Diffuser outlets	Qmax L/s	Qmin L/s	Min plan m	Max plan m	Outlets
VAV-01	SD-01, SD-02, SD-13, SD-14	575.7	230.3	2.525	2.525	4
VAV-02	SD-03, SD-04, SD-15, SD-16	584.4	233.8	2.525	2.525	4
VAV-03	SD-05, SD-06, SD-17, SD-18	585.8	234.3	2.525	2.525	4
VAV-04	SD-07, SD-08, SD-19, SD-20	616.7	246.7	2.525	2.525	4
VAV-05	SD-09, SD-10, SD-21, SD-22	590.2	236.1	2.006	2.976	4
VAV-06	SD-11, SD-12, SD-23, SD-24	539.0	215.6	2.282	2.611	4
VAV-07	SD-25, SD-26, SD-37, SD-38	618.4	247.4	2.525	2.525	4
VAV-08	SD-27, SD-28, SD-39, SD-40	618.4	247.4	2.525	2.525	4
VAV-09	SD-29, SD-30, SD-41, SD-42	618.4	247.4	2.525	2.525	4
VAV-10	SD-31, SD-32, SD-43, SD-44	652.0	260.8	2.525	2.525	4
VAV-11	SD-33, SD-34, SD-45, SD-46	623.2	249.3	2.006	2.976	4
VAV-12	SD-35, SD-36, SD-47, SD-48	580.1	232.0	2.282	2.611	4
VAV-13	SD-49, SD-50, SD-61, SD-62	551.8	220.7	2.151	2.525	4
VAV-14	SD-51, SD-52, SD-63, SD-64	556.0	222.4	2.151	2.525	4
VAV-15	SD-53, SD-54, SD-65, SD-66	557.6	223.0	2.151	2.525	4
VAV-16	SD-55, SD-56, SD-67, SD-68	586.9	234.7	2.151	2.525	4
VAV-17	SD-57, SD-58, SD-69, SD-70	585.1	234.0	1.508	2.976	4
VAV-18	SD-59, SD-60, SD-71, SD-72	540.1	216.0	1.860	2.611	4
VAV-19	SD-73, SD-74, SD-77, SD-78	718.0	287.2	2.873	2.873	4
VAV-20	SD-75, SD-76, SD-79, SD-80	702.6	281.0	2.873	2.873	4

Plan lengths are lower bounds, not installed flex lengths; elevation, bends and slack remain unknown.
VAV symbols and group labels do not establish selected hardware or physical outlet-port geometry.
Source allocation, room load, ADPI, installation and Hong Kong applicability remain under review.